



# Review of Large Site SESC Plan Performance Criteria

February 12, 2015

Brian Lafaille  
RIDEM RIPDES Stormwater Program



THE  
UNIVERSITY  
OF RHODE ISLAND  
COOPERATIVE  
EXTENSION  
RI NEMO






# Soil Erosion and Sediment Control Performance Criteria

1. **Avoid and Protect Sensitive Areas and Natural Features**
2. **Minimize Area of Disturbance**
3. **Minimize the Disturbance of Steep Slopes**
4. **Preserve Topsoil**
5. **Stabilize Soils**
6. **Protect Storm Drain Inlets**
7. **Protect Storm Drain Outlets**
8. **Establish Temporary Controls for the Protection of Post-Construction Stormwater Treatment Practices**
9. **Establish Perimeter Controls and Sediment Barriers**
10. **Divert or Manage Run-on from Up-gradient Areas**
11. **Properly Design Construction Stormwater Conveyance Channels**
12. **Retain Sediment Onsite**
13. **Control Temporary Increases in Stormwater Velocity, Volume, and Peak Flows**
14. **Construction Activity Pollution Prevention Control Measures**
15. **Control Measure Installation, Inspections, Maintenance, and Corrective Actions**

# Soil Erosion and Sediment Control Performance Criteria

1. **Avoid and Protect Sensitive Areas and Natural Features**
2. **Minimize Area of Disturbance**
3. **Minimize the Disturbance of Steep Slopes**
4. **Preserve Topsoil**
5. **Stabilize Soils**
6. **Protect Storm Drain Inlets**
7. **Protect Storm Drain Outlets**
8. **Establish Temporary Controls for the Protection of Post-Construction Stormwater Treatment Practices**
9. **Establish Perimeter Controls and Sediment Barriers**
10. **Divert or Manage Run-on from Up-gradient Areas**
11. **Properly Design Construction Stormwater Conveyance Channels**
12. **Retain Sediment Onsite**
13. **Control Temporary Increases in Stormwater Velocity, Volume, and Peak Flows**
14. **Construction Activity Pollution Prevention Control Measures**
15. **Control Measure Installation, Inspections, Maintenance, and Corrective Actions**

# Performance Criteria No. 10 Divert or Manage Run-on from Up-gradient Areas



Source: USEPA-833-R-06-004 May 2007

# Foundry Parking Lots Construction Project



Source: RIDEM - RIPDES Permitting Program

# Foundry Parking Lots Construction Project



Source: RIDEM - RIDES Permitting Program

# Foundry Parking Lots Construction Project



Source: RIDEM – RIPDES Permitting Program

# RIDOT I-95 Viaduct Project



Source: RIDEM – RIPDES Permitting Program

# RIDOT I-95 Viaduct Project



Source: RIDEM – RIPDES Permitting Program

# RIDOT I-95 Viaduct Project



# RIDOT I-95 Viaduct Project



# RIDOT I-95 Viaduct Project



# RIDOT I-95 Viaduct Project



# Diversion Installed – Problem Alleviated



Source: RIDEM – RIPDES Permitting Program

# Diversion Installed – Pipe Slope Drain



Source: RIDEM – RIPDES Permitting Program

# Diversion Installed – Pipe Slope Drain



Source: RIDEM – RIPDES Permitting Program

# Diversion Installed – Pipe Slope Drain



Source: RIDEM – RIPDES Permitting Program

# Diversion Installed – Pipe Slope Drain



Source: RIDEM – RIPDES Permitting Program

# Diversion Installed – Pipe Slope Drain




Source: RIDEM – RIPDES Permitting Program

# Performance Criteria No. 11 Properly Design Constructed Stormwater Conveyance Channels



# Example: Temporary Diversion Swale



**NOTES:**

1. THE EROSION AND SEDIMENTATION CONTROLS SHOWN ON THE PLANS ARE INTENDED TO REPRESENT THE MINIMUM CONTROLS NECESSARY TO MEET ANTICIPATED SITE CONDITIONS. ADDITIONAL MEASURES SHALL BE IMPLEMENTED AS CONDITIONS WARRANT OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
2. CONTRACTOR SHALL PLACE SILT SOCKS IN ALL EXISTING AND PROPOSED CATCH BASINS UNTIL THE SITE IS STABILIZED.
3. CONTRACTOR SHALL INSTALL AND MAINTAIN CONSTRUCTION ENTRANCES AT ALL POINTS OF EGRESS FROM THE SITE THROUGHOUT CONSTRUCTION.
4. RUNOFF SHALL BE DIRECTED AWAY FROM PROPOSED TREE BOX FILTER AND BIORETENTION AREA VIA TEMPORARY DIVERSIONS UNTIL THE UPSTREAM AREAS ARE STABILIZED. ONCE UPSTREAM AREAS ARE STABILIZED, TEMPORARY DIVERSIONS SHALL BE REMOVED AND RUNOFF SHALL BE DIRECTED TO THE PROPOSED BMP'S.
5. WASHING OF CONSTRUCTION EQUIPMENT IS NOT PERMITTED ON THE SITE. VEHICLE MAINTENANCE ACTIVITIES THAT REQUIRE DRAINING OF OILS, FUEL OR OTHER FLUIDS ARE NOT PERMITTED ON THE SITE.
6. ANY AREAS LEFT EXPOSED FOR A PERIOD OF LONGER THAN 14 DAYS WITHOUT BEING SUBJECT TO CONSTRUCTION ACTIVITY SHALL BE SEEDED TEMPORARILY. EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL UPSTREAM AREAS ARE STABILIZED.

**LEGEND**


- X REMOVE & DISPOSE TREE, DISPOSE OF TREE AND STUMP OFF-SITE.
- ⊙ PROTECT EXISTING TREE TO REMAIN PERFORM EROSION TREE PROTECTION (DLI STD. 91.1.1)
- TDS TEMPORARY DIVERSION SWALE
- TST TEMPORARY SEDIMENTATION TRAP
- L&P LIMIT OF DISTURBANCE
- SILT SOCK

MATCHLINE - SEE SHEET C2.2

Graphic Scale



# Example: Temporary Diversion Swale





**Performance Criteria No. 12**  
**Retain Sediment Onsite**

# **Retain Sediment Onsite: Common Drainage Locations Serving <1 Acre of Disturbance**

**A combination of phasing, stabilization, and conveyances that provide run-off control will be sufficient.**

**Note: In some cases, additional control measures may be required where site conditions warrant or a specific requirement exists in State regulations or Local ordinance. Refer to Performance Criteria No. 13 for additional information.**


# **Retain Sediment Onsite: Temporary Sediment Traps**




**Sediment Traps are Mandatory for Common Drainage Locations  
Where 1-5 Acres of Land Will Be Disturbed**

**Note: If period of disturbance will be greater than six (6) months, a sediment basin would be required.**


# Example: Temporary Sediment Trap




# Example: Temporary Sediment Trap




# Example: Temporary Sediment Trap




# Example: Temporary Sediment Trap



# Example: Temporary Sediment Trap




# Example: Temporary Sediment Trap



| SEDIMENT TRAP # | BOTTOM ELEV. | CLEANOUT MARK ELEV. | WET POOL ELEV. | WEIR CREST ELEV. | DRY POOL MAX. ELEV. | TOP OF BASIN ELEV. | TOP WIDTH |
|-----------------|--------------|---------------------|----------------|------------------|---------------------|--------------------|-----------|
| 1               | 246.00       | 247.8               | 249.00         | 251.00           | 251.46              | 252.00             | 2.5'      |
| 2               | 252.00       | 253.4               | 254.00         | 256.50           | 256.82              | 257.50             | 3.0'      |
| 3               | 259.00       | 260.2               | 261.00         | 263.00           | 263.35              | 264.00             | 2.5'      |
| 4               | 270.00       | 272.8               | 273.00         | 275.00           | 275.47              | 276.00             | 2.5'      |
| 5               | 226.000      | 227.3               | 229.00         | 231.00           | 231.36              | 232.00             | 2.5'      |

**LONGITUDINAL CROSS SECTION**

NOT TO SCALE



**TRANSVERSE CROSS SECTION**

NOT TO SCALE

**TEMPORARY SEDIMENT TRAP DETAIL**


NOT TO SCALE

# Retain Sediment Onsite: **Temporary Sediment Basins**




- **Required for Common Drainage Locations Where >5 Acres of Land Will Be Disturbed**
- **Designs Must Utilize Surface Outlets When Discharging From Temporary Sediment Basins to Maximize Sediment Removal**
- **Required for Common Drainage Locations where 1-5 Acres of Land Will Be Disturbed for Lengths of Time > Six (6) Months.**

# Example: Temporary Sediment Basin





# Example: Temporary Sediment Basin




Pond E


Scale: 1"=30'

Pond F

Scale: 1"=30'




LEVEL SPREADER  
NOT TO SCALE




EMERGENCY SPILLWAY DETAIL  
NOT TO SCALE


| DESCRIPTION                | POND E | POND F |
|----------------------------|--------|--------|
| TOP OF POND ELEVATION      | 62.00  | 45.00  |
| BOTTOM OF POND             | 58.00  | 38.00  |
| 100 YEAR STORM ELEVATION   | 61.00  | 44.47  |
| 10 YEAR STORM ELEVATION    | 58.15  | 41.58  |
| 1 YEAR STORM ELEVATION     | 57.70  | 39.96  |
| MINIMUM HIGH GWT ELEVATION | 34-36  | 39.4   |
| SOIL EVALUATION            | TH 25  | TH 25B |



DETENTION POND TYPICAL CROSS SECTION  
NOT TO SCALE



POND E OUTLET CONTROL MANHOLE E-1  
SCALE: 1"=4"




POND F OUTLET CONTROL MANHOLE (OCMH-PONDF)  
SEE SHEET 14  
SCALE: 1"=4"

| LOCATION | WIDTH | HEIGHT | QUANTITY |
|----------|-------|--------|----------|
| POND E   | 3.0'  | 3.0'   | 4        |
| POND F   | 3.0'  | 3.0'   | 3        |


INSTALLATION NOTES:  
1. UNRAVE THE ANTI-SEEP COLLAR AND ATTACH THE SHIELDS TO THE EDGES TO FORM A SQUARE. (USE THE SHIELDS AND NAILS PROVIDED BY THE MANUFACTURER.)  
2. CUT A ROUND HOLE IN THE CENTER OF THE SQUARE THAT IS SMALLER THAN THE PIPE. THIS WILL ALLOW THE PUMPER TO STRETCH OVER THE PIPE WHEN THE ANTI-SEEP IS INSTALLED ON THE PIPE. THIS SHOULD PROVIDE A TIGHTER WRAP AROUND THE PIPE AND THE ANTI-SEEP.  
3. SLIP THE PIPE THROUGH THE ANTI-SEEP, ADJUST THE SEAL BETWEEN THE PIPE AND THE ANTI-SEEP, CHECK FOR GAPS, AND COMPACT WITH SUITABLE SOIL.

ANTI-SEEP COLLAR  
NOT TO SCALE



POND E WITH OUTLET CONTROL STRUCTURE

POND F WITHOUT OUTLET CONTROL STRUCTURE




LOW FLOW (CPV) OUTLET

| LOCATION | INLET | ORIFICE | DIAMETER |
|----------|-------|---------|----------|
| POND E   | 36.00 | 1.75    |          |
| POND F   | 38.00 | 3.125   |          |

Details - Ponds E & F


# Example: Temporary Sediment Basin

| LOCATION | TOP OF POND ELEV. | WEIR INVERT | WEIR DEPTH |
|----------|-------------------|-------------|------------|
| POND E   | 62.00             | 61.00       | 1'         |
| POND F   | 45.50             | 44.50       | 1'         |



**EMERGENCY SPILLWAY DETAIL**  
NOT TO SCALE

| DESCRIPTION                 | POND E | POND F |
|-----------------------------|--------|--------|
| TOP OF POND ELEVATION       | 62.00  | 45.50  |
| BOTTOM OF POND              | 56.00  | 39.00  |
| 100 YEAR STORM ELEVATION    | 61.00  | 44.47  |
| 10 YEAR STORM ELEVATION     | 59.15  | 41.56  |
| 1 YEAR STORM ELEVATION      | 57.79  | 39.96  |
| SEASONAL HIGH GWT ELEVATION | 54-58  | 39.4   |
| SOIL EVALUATION             | TH G5  | TH G18 |




**DETENTION POND TYPICAL CROSS SECTION**  
NOT TO SCALE

| LOCATION | WIDTH | HEIGHT | QUANTITY |
|----------|-------|--------|----------|
| POND E   | 3.0'  | 3.0'   | 4        |
| POND F   | 3.0'  | 3.0'   | 3        |


**INSTALLATION NOTES:**

1. UNROLL THE ANTI-SEEP AND ATTACH THE BOARDS TO THE EDGES TO FORM A SQUARE. (USE THE BOARDS AND NAILS PROVIDED.) (4'X4' & LARGER)
2. CUT A ROUND HOLE IN THE CENTER OF THE RUBBER THAT IS SMALLER THAN THE PIPE SIZE (APPROX. 25% SMALLER). THIS WILL ALLOW THE RUBBER TO STRETCH OVER THE PIPE WHEN THE ANTI-SEEP IS INSTALLED ON THE PIPE. THIS SHOULD PROVIDE A NEARLY WATERPROOF SEAL BETWEEN THE PIPE AND THE ANTI-SEEP.
3. SLIP THE PIPE THROUGH THE ANTI-SEEP. INSPECT THE SEAL BETWEEN THE PIPE AND THE ANTI-SEEP. CAREFULLY BACKFILL AND COMPACT WITH SUITABLE SOIL.




**ANTI-SEEP COLLAR**  
NOT TO SCALE


NOTE:  
AGRI DRAIN CORP. OR EQUAL



**POND F WITH OUTLET CONTROL STRUCTURE**



**POND F WITHOUT OUTLET CONTROL STRUCTURE**





**LOW FLOW RISER DETAIL**

| INTERNAL ORIFICE SCHEDULE |        |          |
|---------------------------|--------|----------|
| LOCATION                  | INVERT | DIAMETER |
| POND E                    | 56.00  | 1.75"    |
| POND F                    | 39.00  | 2.125"   |

**LOW FLOW (CPV) OUTLET**  
NOT TO SCALE

# Example: Surface Outlet



**Performance Criteria No. 13**  
**Control Temporary Increases in  
Stormwater Velocity, Volume,  
and Peak Flows**

# Goal: Minimize Impacts In the Vicinity of All Points of Discharge:

- Channel Erosion/Scouring means  
Controlling velocities
- Natural Streambank Erosion means  
controlling smaller storms
- Flooding (ex. Overbank, Drainage System)

# The Combination of All Other Performance Criteria Will Be Adequate In the Majority of Cases

- Construction Sequencing/Phasing
- Minimize Area of Disturbance
- Stabilize Soils
- Establish Perimeter Controls and Sediment Barriers
- Divert or Manage Run-on from Upgradient Areas
- Retain Sediment Onsite
  - <1 Acre of Disturbance - No Trap or Basin Required
  - 1- 5 Acres of Disturbance - Sediment Trap
  - >5 Acres of Disturbance - Sediment Basin

Example No. 1  
Overbank Flooding Concerns
















## Example No. 2

# Flooding of Downstream Collection System



# Pre-Development Analysis

## Design Storms



The hydrologic analysis was performed using HydroCAD software for a 24-hour, Type III rainfall event for Washington County (1-year: 2.8 inches, 10-year: 4.9 inches, 100-year: 8.5 inches). Two (2) Design Points were analyzed:

- Design Point 1: RVW Closed Drainage System to Hall Creek
- Design Point 2: CPR Closed Drainage System to Mill Creek

### PRE-DEVELOPMENT ANALYSIS

Under pre-development conditions, the Site was divided into three (3) sub-watersheds contributing to the two (2) Design Points, where peak discharge rates and volumes were evaluated for the 10-year and 100-year storm events. (See Appendix F for "Pre-development Drainage Area Plan" and Appendix C for HydroCAD calculations):

- Sub-watershed "HC-3A" is comprised of 12.6± acres of pasture/grass and some pavement. Runoff from this area flows overland northeasterly into the closed drainage system in Romano Vineyard Way (Design Point 1), where stormwater is conveyed via closed pipe in a southerly direction to an outfall at Hall Creek.
- Sub-watershed "HC-3B" (Pre-2004) is comprised of 3.6± acres of pasture/grass and some pavement. Runoff from this area flows overland northeasterly into the closed drainage system in Romano Vineyard Way (Design Point 1), where stormwater is conveyed via closed pipe in a southerly direction to an outfall at Hall Creek.
- Sub-watershed "MC-2B-2" (Post-2004) is comprised of 9.5± acres of Phase I roof, Pond 3, and landscape areas adjacent to Pond 3. Pond 3 contains an outlet control structure (OCS) along the western banks of the basin. The OCS controls peak runoff out of Pond 3 with a 12-inch pipe from the OCS to the closed drainage system in Commerce Park Road (Design Point 2), where it is conveyed in a southerly direction to Mill Creek.


### POST-DEVELOPMENT ANALYSIS

Under post-development conditions, the Site was divided into eight (8) sub-watersheds contributing to the two (2) previously-described Design Points, where peak discharge rates and volumes were evaluated for the 10-year and 100-year storm events. Four (4) of these sub-watersheds are conveyed to Pond 4 prior to entering Pond 3 and three (3) of these sub-watersheds are conveyed directly to Pond 3. (See Appendix F for "Post-development Drainage Area Plan" and Appendix C for HydroCAD calculations).

#### To Pond 4:

- Sub-watershed "PR-4A" is comprised of 4.6± acres of truck loading and trailer parking and some grass that is conveyed via closed drainage piping to a sediment forebay and bioretention area in Pond 4 then to Pond 3 through a box culvert.
- Sub-watershed "PR-4B" is the 4.4± acre proposed building roof that is conveyed via closed drainage piping to a sediment forebay in Pond 4 then conveyed to Pond 3 through a box culvert.

## Two Design Points



Designer identifies points of discharge and evaluates potential for impacts

# Post-Development Analysis

## 5. HYDROLOGIC ANALYSIS

The hydrologic analysis was performed using HydroCAD software for a 24-hour, Type III rainfall event for Washington County (1-year: 2.8 inches, 10-year: 4.9 inches, 100-year: 8.5 inches). Two (2) Design Points were analyzed:

- Design Point 1: RVW Closed Drainage System to Hall Creek
- Design Point 2: CPR Closed Drainage System to Mill Creek

### PRE-DEVELOPMENT ANALYSIS

Under pre-development conditions, the Site was divided into three (3) sub-watersheds contributing to the two (2) Design Points, where peak discharge rates and volumes were evaluated for the 10-year and 100-year storm events. (See Appendix F for "Pre-development Drainage Area Plan" and Appendix C for HydroCAD calculations):


- Sub-watershed "HC-3A" is comprised of 12.6± acres of pasture/grass and some pavement. Runoff from this area flows overland northeasterly into the closed drainage system in Romano Vineyard Way (Design Point 1), where stormwater is conveyed via closed pipe in a southerly direction to an outfall at Hall Creek.
- Sub-watershed "HC-3B" (Pre-2004) is comprised of 3.6± acres of pasture/grass and some pavement. Runoff from this area flows overland northeasterly into the closed drainage system in Romano Vineyard Way (Design Point 1), where stormwater is conveyed via closed pipe in a southerly direction to an outfall at Hall Creek.
- Sub-watershed "MC-2B-2" (Post-2004) is comprised of 9.5± acres of Phase I roof, Pond 3, and landscape areas adjacent to Pond 3. Pond 3 contains an outlet control structure (OCS) along the western banks of the basin. The OCS controls peak runoff out of Pond 3 with a 12-inch pipe from the OCS to the closed drainage system in Commerce Park Road (Design Point 2), where it is conveyed in a southerly direction to Mill Creek.

### POST-DEVELOPMENT ANALYSIS

Under post-development conditions, the Site was divided into eight (8) sub-watersheds contributing to the two (2) previously-described Design Points, where peak discharge rates and volumes were evaluated for the 10-year and 100-year storm events. Four (4) of these sub-watersheds are conveyed to Pond 4 prior to entering Pond 3 and three (3) of these sub-watersheds are conveyed directly to Pond 3. (See Appendix F for "Post-development Drainage Area Plan" and Appendix C for HydroCAD calculations).

#### To Pond 4:

- Sub-watershed "PR-4A" is comprised of 4.6± acres of truck loading and trailer parking and some grass that is conveyed via closed drainage piping to a sediment forebay and bioretention area in Pond 4 then to Pond 3 through a box culvert.
- Sub-watershed "PR-4B" is the 4.4± acre proposed building roof that is conveyed via closed drainage piping to a sediment forebay in Pond 4 then conveyed to Pond 3 through a box culvert.



Closed Collection System  
and Conveyances at  
capacity, history of  
flooding in area

# Post-Development Analysis

- Sub-watershed "PR-4C" is comprised of 1.0± acre of mostly paved access drive and some grass that is conveyed across a filter strip directly into Pond 4 then to Pond 3 through a box culvert.
- Sub-watershed "PR-4D" is comprised of 2.4± acres of grass/landscape areas associated with Pond 4.



### To Pond 3:

- Sub-watershed "PR-3C" is comprised of 6.2± acres of mostly existing and proposed Pond 3 and the landscape areas and emergency access drive surrounding Pond 3. Two outlet control structures in Pond 3 convey stormwater from this area to Design Point 1 (Romano Vineyard Way) and Design Point 2 (Commerce Park Road).
- Sub-watershed "PR-3B" is comprised of 2.5± acres of truck loading and trailer parking with some grass that is conveyed via closed drainage piping to a sediment forebay in Pond 3. Two outlet control structures in Pond 3 convey stormwater from this area to Design Point 1 (Romano Vineyard Way) and Design Point 2 (Commerce Park Road).
- Sub-watershed "PR-3A" is the 6.2± acre proposed building roof that is conveyed via closed drainage piping to a sediment forebay in Pond 3. Two outlet control structures in Pond 3 convey stormwater from this area to Design Point 1 (Romano Vineyard Way) and Design Point 2 (Commerce Park Road).
- Sub-watershed "PR-3D" is comprised of 9.5± acres of existing roof directly discharging into Pond 3. Two outlet control structures in Pond 3 convey stormwater from this area to Design Point 1 (Romano Vineyard Way) and Design Point 2 (Commerce Park Road).

Table 1: Hydrologic Analysis Summary (See additional details in Appendix C)

| Design Point | Description                    | DESIGN STORM | Peak Flow (cfs) |      | Volume (Ac-ft) |      |
|--------------|--------------------------------|--------------|-----------------|------|----------------|------|
|              |                                |              | EX              | PR   | EX             | PR   |
| 1            | Romano Vineyard Way Hall Creek | 10-YEAR      | 24.5            | 6.7  | 4.4            | 5.9  |
|              |                                | 100-YEAR     | 49.2            | 10.7 | 9.0            | 13.4 |
| 2            | Commerce Park Road Mill Creek  | 10-YEAR      | 2.6             | 2.7  | 4.6            | 6.7  |
|              |                                | 100-YEAR     | 6.0             | 5.6  | 8.7            | 9.9  |

The analysis shows that post-development peak discharge rates are significantly less than pre-development peak discharge rates to Romano Vineyard Way and Design Point 1. Post-development peak discharge rates are roughly equivalent to pre-development peak discharge rates to Commerce Park Road and Design Point 2. These results are conservative, as they negate any infiltration that might occur in the bioretention portions of the basins or the basin sidewalls.



Peak Rates are managed for the 10 yr and 100 yr storms

# Control Velocities and Volumes

## 1.2 Nature and Sequence of Construction Activity

- The Project is estimated to commence in November 2013 (or upon receipt of all necessary permits) with the placement of perimeter erosion and sedimentation controls around the active construction area, followed by minor clearing and grubbing within the limit of disturbance. Anticipated erosion controls at the onset of construction include a construction entrance, placement of silt fence along all down-gradient slopes within the subject property, silt sack sediment traps in existing catch basins in the vicinity of the project, and hay bales at the existing inlets and outlets to Pond 3.
- If construction activities are temporarily halted for more than 14 days, the disturbed areas will be stabilized with temporary seed.
- Earthwork associated with building pad preparation and truck loading and trailer parking is anticipated immediately following placement of erosion controls. Installation of the stormwater management system will be coordinated with these earthwork activities to ensure that stormwater quality and quantity is managed throughout construction activities. Temporary sediment basins and phased construction within Pond 3 are required to achieve these goals.
- As each bioretention area is completed, silt fence will be installed around the perimeter of each immediately after completion of construction to protect them from sediment transport from construction runoff and compaction from construction equipment.
- Paving of parking and loading areas and access drives and placement of loam, seed, and landscaping is expected to be completed by June 2014. The construction of the building itself is not anticipated at this time or in the near future.

### Phase II – DURING EARTHWORK

- Describe phase:  
Immediately following the placement of the erosion controls, minor clearing and grubbing within the proposed limit of disturbance is anticipated, as most of this area was already cleared during previous permitting of the Site. Construction will commence with the installation of the utilities infrastructure and the re-grading of Pond 3. A binder course in pavement areas is anticipated to be completed during this phase.

The Contractor shall employ a phased approach to re-grading Pond 3 and re-installing/lowering its outlet control structure, as existing roof runoff directed to Pond 3 must continue throughout construction. Phasing may include temporary sediment basins near Pond 3, sheeting or other methodologies for isolating the construction work zone from the active stormwater system, and erosion control devices (gabions, stone check dams, or haybales) to prevent sediments from exiting Pond 3 during construction.



Sequencing



Phasing

# Control Velocities and Volumes

## 2.12 Retain Sediment On-Site and Control Dewatering Practices

Sediment traps, basins, and barriers are used to retain sediment on the site to protect streams, lakes, drainage systems, and adjacent property. These devices are used at the outlets of channels, diversions, and other runoff conveyance measures to allow sediment-filled water to pool and sediment to settle. These measures are often used as the last line of defense to stop sediment from leaving the site.

A sediment trap or basin shall be installed, and maintained, as depicted on the approved plan set and in accordance with the Rhode Island Soil Erosion and Sediment Control Handbook (as amended) or the RI Department of Transportation Standard Specifications for Road and Bridge Construction (as amended).

The dewatering of non-contaminated non-stormwater (i.e. groundwater) or accumulated precipitation discharge of sediment-laden water into storm drains, streams, lakes or wetlands prior to sediment removal is prohibited. A sediment trap or basin shall be installed, and maintained, as depicted on the approved plan set and in accordance with the Rhode Island Soil Erosion and Sediment Control Handbook (as amended) or the RI Department of Transportation Standard Specifications for Road and Bridge Construction (as amended).

The dewatering of contaminated non-stormwater cannot be discharged without obtaining a Rhode Island Department of Environmental Management RIPDES discharge permit to do so. If dewatering of contaminated water is anticipated at the site, appropriate permits must be obtained in advance.

- Sediment trap(s) may be installed in Pond 3 to retain sediment during construction. Because Pond 3 must remain operational throughout construction and the contractor will need to modify Pond 3 in phases, no single location for these sediment traps can be identified on the plan set, but rather, it is left to the discretion of the contractor. A sediment trap detail is provided in the plan set and designed in accordance with the RI Soil Erosion and Sedimentation Control Handbook.
- Visible floating solids or foam shall not be discharged.
- Velocity dissipation devices shall be used at all points where dewatering water is discharged.



# Control Velocities and Volumes

## 2.6 Control Stormwater Flowing Onto and Through the Project

Structural BMPs are used to divert flows from exposed soils, retain or detain flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site.


BMPs shall be installed as depicted on the approved plan set and in accordance with the Rhode Island Soil Erosion and Sediment Control Handbook (as amended) or the RI Department of Transportation Standard Specifications for Road and Bridge Construction.

- Structural practices, such as temporary sediment basins and diversion dikes are anticipated to be required during construction to modify Pond 3, because roof drain connections into Pond 3 (installed in 2004) will continue to discharge runoff into Pond 3 throughout construction. Pond 3 changes include excavation of two feet of material and widening to increase storage capacity and accommodate the anticipated increase in the 100-year storm event.





# The Design Professional is Responsible for Evaluating the Need for Additional Controls.



# Next Steps

## ➤ Further Training Sessions Planned

- Design Professionals
- Municipalities
- RIDOT
- Contractors

# Next Steps

- Update Toolbox
  - Internal SESC Plan Review Checklist
  - Appendix A Checklist Revision
  - RI Model SESC Plan
  - RI Stormwater Management Guidance for Individual Single-Family Residential Lot Development

